



राजस्थान केन्द्रीय विश्वविद्यालय
Central University of Rajasthan
NH-8, Bandarsindri, Kishangarh-305817, Ajmer(Raj.)

Financial Bid

Name of Work: Repair & Maintenance of Court yard of Hostel Building No.03 at Central University of Rajasthan.

NIT No. CURAJ/R/F.143/2022/ 3651

Date: 20.12.2022

S. N	Description	Qty	Unit	Rate	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:				
1.2	All kinds of soil	608.00	sqm		
2	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.				
2.1	40 mm thick with 20 mm nominal size stone aggregate	608.00	sqm		
3.0	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
3.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	45.60	Cum		
4	Providing and fixing glass strips in joints of terrazo/ cement concrete floors.				
4.1	40 mm wide and 4 mm thick	1100.00	Mtr.		
5	Providing and fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, of size 800 x 600x50 mm, reinforced with 8 mm dia four nos longitudinal & 9 nos cross sectional T.M.T. hoop bars, including providing edge binding with M.S. flats of size 50 mm x 1.6 mm complete, all as per direction of Engineer-in-charge.	88	Each		
	Total Amount inclusive GST & others			Rs.	

Note: The Goods and Service Tax, Turnover Tax, Excise Duty, Work Contract Tax, Or any other Tax as applicable shall be paid by the contractor himself. The contractor shall quote his rates considering all such Taxes.

Seal & Signature of Bidder
Date: