FINANCIAL BID

Schedule-I

NIT No. CURAJ/R/F.143/2022/3503

Name of Work: Repair and Maintenance work of Academic Buildings at Central University of Rajasthan.

S. N	Description	Qty	Unit	Rate	Amount
	Acrylic emulsion, having VOC content less				
1	than 50 grams/ litre Code:803	515.69	Ltr		
	Textured exterior paint				
2	DSR Code:8507	3093.67	Ltr		
	White cement based putty				
3	Code:824	5103	kg		
	Acrylic distemper 1st quality, having VOC				
	content less than 50 grams/ litre				
4	DSR Code:0802	689.28	kg		
	Synthetic enamel paint in all shades except				
	black or chocolate shade				
5	DSR Code:834	155.33	Ltr		
6	Portland Cement (PPC -43 Grade)	140.00	Bags		
7	Coarse sand	30.00	Cum		
	Total Amount inclusive GST and others			Rs.	

<u>Note</u>:- Rate quoted by Contractor should include all the factors e.g. Cartage, Wastage, Excise, all types of taxes such as GST as applicable, Contractor's overhead & profit etc.. Nothing extra will be paid to Contractor.

Seal & Signature of Bidder Date:

Date: 13.12.2022

FINANCIAL BID

Schedule-II

Date: 13.12.2022

NIT No. CURAJ/R/F.143/2022/3503

Name of Work: Repair and Maintenance work of Academic Buildings at Central University of Rajasthan.

S. N	Description	Qty	Unit	Rate	Amount(Rs.)
	Providing manpower for Removing dry or oil				
	bound distemper, water proofing cement paint				
	and the like by scrapping, sand papering and				
	preparing the surface smooth including				
	necessary repairs to scratches etc. complete				
	Note: Labour rate to be quoted by the bidder				
	for the purpose including T&P, service chrges				
	and GST, Material will be provided by the	2700.00	~		
1	University.	2500.00	Sqm		
	Providing manpower for Repairs to plaster of				
	thickness 12 mm to 20 mm in patches of area				
	2.5 sq.meters and under, including cutting the				
	patch in proper shape, raking out joints and				
	preparing and plastering the surface of the				
	walls complete, including disposal of rubbish				
	to the dumping ground, all complete as per				
	direction of Engineer-in-Charge.				
	Note: Labour rate to be quoted by the bidder				
	for the purpose including T&P, service chrges				
2	and GST, Material will be provided by the				
2	University.				
2.1	With cement mortar 1:4 (1cement: 4 coarse	1000.00	a		
2.1	sand)	1000.00	Sqm		
	Providing manpower for Finishing walls with				
	textured exterior paint of required shade:				
	Note: Labour rate to be quoted by the bidder				
	for the purpose including T&P, service charges				
2	and GST, Material will be provided by the				
3	University.				
	Old work (Two or more coats on existing				
2.1	cement paint surface applied @ 3.28 ltr/10	0421.01	Com		
3.1	sqm.	9431.91	Sqm		

	Providing manpower for Wall painting with premium acrylic emulsion paint of interior grade, including applying additional coats wherever required to achieve even shade and colour.				
4	Note: Labour rate to be quoted by the bidder for the purpose including T&P, service chrges and GST, Material will be provided by the University.				
4.1	One coat	13570.75	Sqm		
5	Providing manpower for Distempering with 1st quality acrylic distemper (ready-made) of required shade and colour complete. Note: Labour rate to be quoted by the bidder for the purpose including T&P, service chrges and GST, Material will be provided by the University.	13370.73	Sqiii		
5.1	One or more coats on old work	6892.83	Sqm		
6	Providing manpower for applying white cement based putty of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete Note: Labour rate to be quoted by the bidder for the purpose including T&P, service chrges and GST, Material will be provided by the University. Providing manpower for Painting with synthetic enamel paint of required colour to give an even shade: Note: Labour rate to be quoted by the bidder for the purpose including T&P, service chrges	3500.00	Sqm		
7	and GST, Material will be provided by the University.				
7.1	One or more coats on old work	2000.00	Sqm		
8	Providing manpower for Painting (one or more coats) on rain water, soil waste and vent pipes and fittings with synthetic enamel paint on old work: Note: Labour rate to be quoted by the bidder for the purpose including T&P, service chrges and GST, Material will be provided by the University.		~ 4		
8.1	100 mm diameter pipes	1000.00	Mtr.		
0.1	Total Amount inclusive GST and others	1000.00	2.241	Rs.	

Note: Rate quoted by Contractor should include all the factors e.g. T&P, Cartage, Excise, all types of taxes such as GST as applicable, Contractor's overhead & profit etc.. Nothing extra will be paid to Contractor.

Seal & Signature of Bidder Date: