

FINANCIAL BID

Name of Work: Supply, Installation, Testing & Commissioning of LED Signage Board (LED Channel letter with support structure) at Central University of Rajasthan.

S.NO.	ITEM DESCRIPTION	UNIT	QTY.	RATE (in Rs.) Incl. GST	AMOUNT (in Rs.) Incl. GST
1	Design, Supply, installation, testing and commissioning of Letters/Logo/Alphabets of 3 D Type using 5 MM RED/WHITE color Imported Acrylic Sheet of A Cast / Astariniagar make, the letters will be in english, as approved by EIC, the area will be calculated on the basis of length and breadth of complete Red/White Color Sheet including wastage	Sq.Ft.	400		
2	Providing & Fixing as per design, Back and Base Letters of the required size made of 1 MM thick (imported) aluminum channel, back side of 4 MM ACP Sheet of Aludecor/Alex/Alstrong along with Water Proof Material with embosing Aluminium Channel 4 inch as required, with proper fixing at site as per direction and approval of EIC, include design, transportation and installation work, the area of letter will be calculated on the basis of length and breadth of complete back sheet used including waste	Sq.Ft.	400		
3	Providing , Fixing, Wiring and testing of 1.5 Watt 6000 - 8000 K (3 SMD) LED of red color of OSRAM/GE/SAMSUNG inside letters/alphabets/logo, the LED's must be of minimum 5 Years Warranty	Each	4500		
4	Supply, Installation, Testing and Commissioning of Water Proof LED Controller Transformer of 300 Watt Make Hi Light/Union/Neenjas, incl. internal wiring as reqd. minimum 5 years Warranty on LED Controller	Each	25		
5	Supply, Fixing, Testing & Commissioning of suitable capacity distribution box along with MCB's Connectors, Timer, Contactor, etc reqd at site as per direction of EIC	1	Job		
6	Suuply, Laying, Testing & Commissioning of 3 Core 4 Sq.mm. Armored PVC insulated XLPE Aluminium Cable complete with glands, lugs etc as reqd at site & directions of EIC.	R/Meter	200		
7	Providing and Fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. such as (M.S. Strcuture 50 mm x 50 mm x 6 mm complete with all vertical and horizontal supports including required welding, bolt, nut, washer for back support of the entire signage, with front frame of 50 mm x 25 mm x 3 mm Rectanglar M.S.hollow Tubes for fixing the Logo/Letters/Alphabets, complete with Two Coat of Enamel Paint) and as per directions of Engineer-In-Charge. (The contractor has to				

	provide structural drawing and nothing extra shall paid on this account).				
7.1	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	4000		
8	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, including cost of centering, shuttering, finishing and reinforcement (note: Extra cement up to 10% of the minimum specified cement content is inclusive)				
8.1	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	4		
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
9.1	Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	700		
	Total Amount of Item 1 to 9 (incl. GST) in Rs				

Seal & Signature of Bidder :

Name of Firm:

*****END OF FINANCIAL BID*****